



**PERMIT TO CONSTRUCT
Onsite Wastewater System**

File Nbr **2022110009**
County: Colleton

Name: TYLER SGRO
Type Facility: MOBILE HOME
Subdivision:
Block: Lot:

Address:
NORTH CHARLESTON, SC 29405
Site: HALYARD RD
EHRHARDT, SC

Program Code³⁶⁰
System Code: 100
TM No.: 070-00-00-035.000
Water Supply: PRIVATE

PERMIT TO CONSTRUCT SYSTEM SPECIFICATIONS

Daily Flow (gpd): 480 **Tank Sizes (gal):** Septic Tank: 1000 Pump Chamber: Grease Trap:
LTAR: .60 **Trenches:** Length (ft): 268 Width (in): 36 Max. Depth (in): 33 Agg. Depth (in): 14
Min Pump Capacity: gpm at ft. of Head Alternative Product:

SPECIAL INSTRUCTIONS/CONDITIONS

THIS PERMIT IS SITE SPECIFIC. ANY CHANGES TO THE SYSTEM MUST BE APPROVED BY DHEC. ALTERNATIVE TRENCH PRODUCTS APPROVED UNDER STATE RULES AND REGULATIONS MAY BE SUBSTITUTED. ANY UNAPPROVED CHANGES WILL VOID THIS PERMIT.

Installers must contact the local Environmental Affairs office by 10:00 AM the day before installation to schedule a time for the final inspection. If a Department representative does not arrive within 30 minutes of the schedule time, the installer may complete the final inspection. When a contractor self-inspection occurs, the installer must complete the DHEC form 3978, Approval to Operate Contractor Self-Inspection. The installer must submit the DHEC form 3978 to the Department within 2 business days of completion of the installation.

- All applicable setbacks set forth in Regulation 61-56 apply.
- Do not install under wet soil conditions.
- Do not cut, fill, bulldoze, scrape or change the grade of the natural soils in the septic system area.
- No parking, driving, building or paving over the area of septic system before or after installation.
- Pre-construction conference required for property owners who wish to install their own system.
- 75' setback from all private wells. 100' setback from public wells..

PERMIT TO CONSTRUCT SYSTEM DIAGRAM

(NTS)

See attached design

Issued/Revised By: Tee Thompson

Date: 12/01/2022

This Permit is Appealable Under the Administrative Procedures Act.

This permit will expire and become null and void five (5) years from the issuance date.

There may be an Additional Fee for Changes in this Permit that Require a Site Reevaluation.



APPROVAL TO OPERATE

Department Staff Inspection - Onsite Wastewater System

File Nbr: **2022110009**

County: **Colleton**

Name: TYLER SGRO
Type Facility: MOBILE HOME
Subdivision
Block: Lot:

Address:
NORTH CHARLESTON, SC 29405
Site: HALYARD RD
EHRHARDT, SC

Program Code: 360
System Code:
TM No. 070-00-00-035.000
Water Supply: PRIVATE

ACTUAL INSTALLATION

(NTS)

FINAL APPROVAL

| | |
|-----------------------|--------------------------|
| Installer: | |
| Septic Tank Mfg: | Tank Size (gal): |
| Pump Chbr Mfg: | Pump Chamber Size (gal): |
| Pump Mfg: | |
| Pump Model: | Elevation Readings: |
| Grease Trap Mfg: | Plumbing Stubout: |
| Alternative Product: | Septic Tank Inlet: |
| Aggregate Type: | Septic Tank Outlet: |
| Aggregate Depth (in): | Pump Chamber Inlet: |
| Trench Width (in): | Line No. |
| Trench Depth (in): | _____ |
| Fill Cap: | _____ |
| Fill Cap Depth (in): | _____ |
| Well Installed: | _____ |
| Well Dist (ft): | _____ |
| Building Dist (ft): | _____ |
| Property Dist (ft): | _____ |
| Water Dist (ft): | _____ |

Comments:

Licensed Installer
Printed Name _____ License No. _____

I hereby certify the system was installed in accordance with the referenced permit and R.61-56 and is in an exposed condition ready for inspection.

Licensed Installer Signature _____ Date _____

Office Use Only

APPROVAL BY DHEC TO OPERATE

THIS CERTIFICATE OF FINAL APPROVAL IN NO WAY GUARANTEES THE LIFE OF THE SYSTEM OR THAT IT WILL FUNCTION PROPERLY UNDER ANY OR ALL CONDITIONS

Approved By: _____ Date: _____